From: Grifftek
To: Bill Griffin;
cc: grifftek @ gmail;
Subject: Fw: detail
Date: Sunday, November 22, 2009 1:44:50 PM
Attachments: revised_details.pdf

----- Original Message -----
From: Roberto Graciano
To: Grifftek
Sent: Sunday, November 22, 2009 11:03 AM
Subject: detail

Basically, those short walls have to be re-build per drawings. Temporary support roof rafters, re-notch the rafters, re-buils studs, put 2x4 on top of ceiling joists etc. The only issue or problem that may occur is that the notch on rafters may be too extreme having a weak point. It that is the case, you need to build a double wall only on 2nd lever per details shown. This will take the gravity loads. The lateral loads will be taken up original wall. Here is the detail.